

**Alabama Department of Transportation
Proposal Item Summary**

019. IM-IMGR-HSIP-I065(517)

JEFFERSON COUNTY

Contract Time: 80 Working Days

DBE Goal Percent: 1.00

for constructing Pavement Rehabilitation and Guardrail Safety Improvements (Planing, Resurfacing, Guardrail Installation, and Traffic Stripe) on I-65 from a point north of the 47th Avenue Overpass (MP 265.200) in Birmingham to a point south of the Mount Olive Road Interchange (MP 271.500) in Fultondale. Length 6.300 mi.

The Bracket Estimate on this project is from \$4,273,048 to \$5,222,615.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	54	SQYD	Removing Concrete Sidewalk
206D001	14,965	LF	Removing Guardrail
206D003	38	LF	Removing Curb And Gutter
206E008	46	Each	Removing Guardrail End Anchor (All Type)
210D001	615	CUYD	Borrow Excavation (Loose Truckbed Measurement)
403B001	575	Ton	Micro-Surfacing Seal Coat, Type III
408B000	286,342	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	12,887	Ton	Polymer Modified Open Graded Friction Course
420B000	51,543	Gal	Open Graded Friction Course Tack Coat
424A283	600	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424A286	600	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
432A000	128,531	SQYD	High Density Mineral Bond
433A000	45,999	SQYD	Scrub Seal
460A003	4,000	LB	Patching (Samiscreed)
600A000	1	LS	Mobilization
618A000	67	SQYD	Concrete Sidewalk, 4" Thick
618C001	60	SQFT	Detectable Warning Surface
618D000	60	SQYD	Curb Ramp
630A001	2,270	LF	Steel Beam Guardrail, Class A, Type 2
630A018	12,695	LF	Steel Beam Guardrail, Class A, Type 2 (Double Faced Median Barrier)
630C001	18	Each	Guardrail End Anchor, Type 8
630C079	8	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	20	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	27,465	LF	Guardrail Reset
650A000	214	CUYD	Topsoil
654A001	811	SQYD	Solid Sodding (Bermuda)
665G000	500	Each	Sand Bags
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	500	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 224,800.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	24	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B027	146	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B063	12,998	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)

Item No.	Quantity	Units	Description
701B207	12,650	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	47	Mile	Broken Temporary Traffic Stripe
701C001	48	Mile	Solid Temporary Traffic Stripe
701G142	1,901	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	951	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	951	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	1,901	LF	Solid Traffic Stripe Removed (Plastic)
701H006	2,192	LF	Broken Traffic Stripe Removed (Plastic)
703A002	14,911	SQFT	Traffic Control Markings, Class 2, Type A
703A011	121	SQFT	Traffic Control Markings, Class W, Type A
703B002	996	SQFT	Traffic Control Legends, Class 2, Type A
703D001	364	SQFT	Temporary Traffic Control Markings
705A030	4,003	Each	Pavement Markers, Class A-H, Type 2-C
705A031	1,718	Each	Pavement Markers, Class A-H, Type 1-A
705A032	351	Each	Pavement Markers, Class A-H, Type 1-B
710A160	18	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B021	26	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
710C000	1	LS	Removal Of Existing Roadway Signs
730H001	2,800	LF	Loop Wire
731A001	2	Each	Traffic Counting Units, Type B
731A002	2	Each	Traffic Counting Units, Type C
731B000	2	Each	Pole for Mounting Traffic Detection Equipment
740B000	3,948	SQFT	Construction Signs
740C000	90	SQFT	Special Construction Signs
740D000	650	Each	Channelizing Drums
741C010	4	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2