

**Alabama Department of Transportation  
Proposal Item Summary**

**022. NH-0002(593)**

**LAUDERDALE COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 5.00

for constructing the Micro-Milling, Resurfacing, Guardrail Installation, and Traffic Stripe on SR-2 (US-72) from 0.060 mile west of the junction of Meadow Lane to 0.230 mile east of the junction of Wheeler Hills Road west of Rogersville. Length 2.577 mi.

The Bracket Estimate on this project is from \$1,704,794 to \$2,083,637.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206E008	3	Each	Removing Guardrail End Anchor (All Type)
405A000	11,604	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	116,036	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A340	2,598	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A360	9,131	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	1,037	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	1,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	11	Mile	Scoring Bituminous Pavement Surface
430B042	1,046	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
630C079	1	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	950	LF	Guardrail Reset
631E001	1	Each	Guardrail End Anchor, Type 8, Reset
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 91,000.00)
701A227	6	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	6	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	5,550	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	10	Mile	Broken Temporary Traffic Stripe
701C001	21	Mile	Solid Temporary Traffic Stripe
701G142	669	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	669	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	669	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	1,338	LF	Solid Traffic Stripe Removed (Plastic)
701H006	669	LF	Broken Traffic Stripe Removed (Plastic)
703A002	626	SQFT	Traffic Control Markings, Class 2, Type A
703B002	292	SQFT	Traffic Control Legends, Class 2, Type A
703D001	824	SQFT	Temporary Traffic Control Markings
705A030	370	Each	Pavement Markers, Class A-H, Type 2-C
740B000	1,177	SQFT	Construction Signs

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
740D000	100	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit