

**Alabama Department of Transportation
Proposal Item Summary**

028. RASTPNU-0420(250)

BIBB COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-2 (West Ashby Road) from the junction of SR-25 to the junction of SR-139 in Brierfield. Length 5.435 mi.

The Bracket Estimate on this project is from \$1,433,055 to \$1,751,511.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
401B108	63,800	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	5,400	Gal	Tack Coat
407B000	11	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A051	63,800	SQYD	Planing Existing Pavement (Approximately 0.00" Thru 1.0" Thick)
424A340	6,810	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	1,200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	3,600	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,700	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 77,000.00)
701A231	11	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	22	Mile	Solid Temporary Traffic Stripe
703A002	480	SQFT	Traffic Control Markings, Class 2, Type A
703B002	137	SQFT	Traffic Control Legends, Class 2, Type A
703D001	80	SQFT	Temporary Traffic Control Markings
705A032	95	Each	Pavement Markers, Class A-H, Type 1-B
705A037	360	Each	Pavement Markers, Class A-H, Type 2-D
740B000	364	SQFT	Construction Signs
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car