

**Alabama Department of Transportation
Proposal Item Summary**

032. STPAA-0167(516)

COFFEE COUNTY

Contract Time: 75 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-167 from the junction of SR-12 (US-84/Boll Weevil Circle) in Enterprise to the junction of CR-154. Length 8.177 mi.

The Bracket Estimate on this project is from \$3,199,890 to \$3,910,977.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$29.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	98	SQYD	Removing Concrete Driveway
209A000	1	Each	Mailbox Reset, Single
210D021	3,000	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	648	STA	Machine Grading Shoulders
405A000	35,608	Gal	Tack Coat
407B000	12	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	145,380	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A361	13,931	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	430	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	7,602	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	4,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	13	Mile	Scoring Bituminous Pavement Surface
430B043	105	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	1,900	LF	Steel Beam Guardrail, Class A, Type 2
630C080	22	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	2,000	CUYD	Topsoil
652A100	9	Acre	Seeding
652C000	102	Acre	Mowing
656A010	9	Acre	Mulching
659C002	1,000	SQYD	Erosion Control Product, Type S2
665A000	9	Acre	Temporary Seeding
665B001	27	Ton	Temporary Mulching
665J002	2,000	LF	Silt Fence
665O001	2,000	LF	Silt Fence Removal
665Q002	2,000	LF	Wattle
666A001	9	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 171,000.00)
701A227	18	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	11	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	6	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701B207	5,539	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	27	Mile	Broken Temporary Traffic Stripe
701C001	98	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	12,056	SQFT	Traffic Control Markings, Class 2, Type A
703B002	919	SQFT	Traffic Control Legends, Class 2, Type A
703D001	5,526	SQFT	Temporary Traffic Control Markings
705A030	451	Each	Pavement Markers, Class A-H, Type 2-C
705A032	1,936	Each	Pavement Markers, Class A-H, Type 1-B
705A037	485	Each	Pavement Markers, Class A-H, Type 2-D
705A038	1,600	Each	Pavement Markers, Class A-H, Type 2-E
740B000	2,261	SQFT	Construction Signs
740C000	27	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car
742A001	2	Each	Portable Changeable Message Sign, Type 2