

**Alabama Department of Transportation
Proposal Item Summary**

044. ATRP2-57-2020-057

RUSSELL COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 2.00

for constructing the Acceleration Lane on SR-1 (US-431) at the CR-4 (Prudence Road) Underpass northwest of Pittsview. Length 0.227 mi.

The Bracket Estimate on this project is from \$111,814 to \$136,662.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210A000	279	CUYD	Unclassified Excavation
210D001	107	CUYD	Borrow Excavation (Loose Truckbed Measurement)
305B077	410	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	120	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A366	95	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	127	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B691	127	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
665F000	25	Each	Hay Bales
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 6,500.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	500	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	1	Mile	Solid Temporary Traffic Stripe
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
703A002	245	SQFT	Traffic Control Markings, Class 2, Type A
703C001	60	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D001	245	SQFT	Temporary Traffic Control Markings
705A030	114	Each	Pavement Markers, Class A-H, Type 2-C
740B000	510	SQFT	Construction Signs
740D000	75	Each	Channelizing Drums
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit