

**Alabama Department of Transportation
Proposal Item Summary**

004. ERPR-9050(900)

PERRY COUNTY

Contract Time: 45 Working Days

for constructing the Permanent Restoration (Slide Repair, Planing, Resurfacing, Guardrail Installation, and Traffic Stripe) on SR-14 at a point 1.250 miles west of the junction of SR-175 northeast of Marion. Length 0.128 mi.

The Bracket Estimate on this project is from \$716,019 to \$875,135.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$15.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201B001	1	Acre	Selective Clearing
206D001	200	LF	Removing Guardrail
206E019	6	Each	Removing Guardrail End Anchor (Type 10)
210D021	27	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
219C003	489	SQYD	Special Filter Blanket, Geotextile
305B079	50	Ton	Crushed Aggregate,Section 825,Type A,For Miscellaneous Use
405A000	258	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	2,579	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A340	213	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	75	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	1	Mile	Scoring Bituminous Pavement Surface
430B050	74	Ton	Aggregate Surfacing(ALDOT#1)
570A000	412	SQYD	Soil Nail Wall
570B000	824	CUYD	Excavation For Soil Nail Wall
600A000	1	LS	Mobilization
610D003	167	SQYD	Filter Blanket, Geotextile
630A001	200	LF	Steel Beam Guardrail, Class A, Type 2
630C080	6	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	725	LF	Guardrail Reset
654A001	167	SQYD	Solid Sodding (Bermuda)
665A000	1	Acre	Temporary Seeding
665B001	1	Ton	Temporary Mulching
665E000	780	SQYD	Polyethylene
665F000	50	Each	Hay Bales
665J002	330	LF	Silt Fence
665N000	75	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	330	LF	Silt Fence Removal
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 59,000.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C001	1	Mile	Solid Temporary Traffic Stripe
705A037	91	Each	Pavement Markers, Class A-H, Type 2-D
726A000	410	LF	Portable Concrete Safety Barriers, Type 6
726A001	20	LF	Portable Concrete Safety Barriers, Type 6-A
726D025	2	Each	Portable Impact Attenuator Assembly (Unidirectional,TL-3)

Item No.	Quantity	Units	Description
740B000	482	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	25	Each	Cones (36 Inches High)
740I002	2	Each	Warning Lights, Type B
740K000	2	Each	Area Light
740M001	25	Each	Ballast For Cone
740P000	1	LS	Portable Rumble Strip
742A001	2	Each	Portable Changeable Message Sign, Type 2
757A001	2	Each	Portable Traffic Signal, Type 2