

**Alabama Department of Transportation  
Proposal Item Summary**

**010. HSIP-0015(539)**

**COVINGTON COUNTY**

Contract Time: 30 Working Days

for constructing the Additional Turn Lane and Intersection Modifications on SR-15 (US-29) at SR-137 southwest of Carolina. Length 0.230 mi.

The Bracket Estimate on this project is from \$357,639 to \$437,114.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
210A000	1,209	CUYD	Unclassified Excavation
210D021	262	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
230A000	6	RBST	Roadbed Processing
301A025	1,976	SQYD	Crushed Aggregate Base Course, Type B, Road Mixed, 6" Compacted Thickness
401A000	1,886	SQYD	Bituminous Treatment A
405A000	984	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B000	4,242	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
424A356	273	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	25	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	194	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	308	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	1	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
652C000	3	Acre	Mowing
654A001	3,032	SQYD	Solid Sodding (Bermuda)
665J002	50	LF	Silt Fence
665O001	50	LF	Silt Fence Removal
665Q002	150	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 18,020.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	180	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	2	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G252	300	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	3,851	SQFT	Traffic Control Markings, Class 2, Type A
703B002	45	SQFT	Traffic Control Legends, Class 2, Type A

Item No.	Quantity	Units	Description
703D001	3,523	SQFT	Temporary Traffic Control Markings
705A030	15	Each	Pavement Markers, Class A-H, Type 2-C
705A032	103	Each	Pavement Markers, Class A-H, Type 1-B
705A037	15	Each	Pavement Markers, Class A-H, Type 2-D
705A038	311	Each	Pavement Markers, Class A-H, Type 2-E
707H001	75	LF	Raised Curb Channelizer, White
710A160	94	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B021	98	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	526	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	500	Each	Cones (36 Inches High)
740F002	2	Each	Barricades, Type III
740M001	500	Each	Ballast For Cone
742A001	2	Each	Portable Changeable Message Sign, Type 2