

**Alabama Department of Transportation
Proposal Item Summary**

015. IM-I020(360)

CALHOUN COUNTY

Contract Time: 65 Working Days

DBE Goal Percent: 1.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on I-20 from the SR-21 (Exit 185) Interchange in Oxford to the Cleburne County Line. Length 8.000 mi.

The Bracket Estimate on this project is from \$3,518,103 to \$4,299,904.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	200	Gal	Tack Coat
408B000	294,635	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	17,100	Ton	Polymer Modified Open Graded Friction Course
420B000	39,703	Gal	Open Graded Friction Course Tack Coat
424B285	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
432A000	92,814	SQYD	High Density Mineral Bond
490A000	1,036	SQYD	Blast Cleaning
490B003	1,036	SQYD	Bridge Deck Overlay
490D000	100	SQFT	Bridge Deck Spall Repair
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 214,000.00)
701A227	18	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	17	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	22	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B027	386	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B207	7,868	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	43	Mile	Broken Temporary Traffic Stripe
701C001	67	Mile	Solid Temporary Traffic Stripe
701G142	4,398	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	3,626	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	3,626	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	7,252	LF	Solid Traffic Stripe Removed (Tape)
701H007	4,398	LF	Broken Traffic Stripe Removed (Tape)
701H012	386	LF	Dotted Traffic Stripe Removed (Tape)
703A002	8,600	SQFT	Traffic Control Markings, Class 2, Type A
703B002	140	SQFT	Traffic Control Legends, Class 2, Type A
705A030	1,450	Each	Pavement Markers, Class A-H, Type 2-C
705A031	850	Each	Pavement Markers, Class A-H, Type 1-A
705A032	570	Each	Pavement Markers, Class A-H, Type 1-B
731A000	3	Each	Traffic Counting Units, Type A
731B000	4	Each	Pole for Mounting Traffic Detection Equipment
740B000	2,222	SQFT	Construction Signs
740C000	36	SQFT	Special Construction Signs
740D000	400	Each	Channelizing Drums
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2