

**Alabama Department of Transportation
Proposal Item Summary**

025. STPAA-0069(564)

MARSHALL COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 8.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-69 from the SR-53 (US-231) Underpass to the junction of North Main Street in Arab. Length 0.949 mi.

The Bracket Estimate on this project is from \$569,308 to \$695,821.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	130	SQYD	Removing Concrete Sidewalk
206D001	100	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
405A000	1,984	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	24,788	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	1,674	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	62	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424C364	500	Ton	Superpave Bituminous Concrete Base Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
614A000	52	CUYD	Slope Paving
618C001	96	SQFT	Detectable Warning Surface
618D000	44	SQYD	Curb Ramp
630A001	100	LF	Steel Beam Guardrail, Class A, Type 2
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	1,000	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 57,500.00)
701A227	3	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B027	220	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B063	1,500	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	1,078	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	8	Mile	Solid Temporary Traffic Stripe
701G146	423	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	423	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	633	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	845	LF	Solid Traffic Stripe Removed (Tape)
701H007	423	LF	Broken Traffic Stripe Removed (Tape)
703A002	5,060	SQFT	Traffic Control Markings, Class 2, Type A
703B002	359	SQFT	Traffic Control Legends, Class 2, Type A
703B011	45	SQFT	Traffic Control Legends, Class W, Type A

Item No.	Quantity	Units	Description
703D001	3,762	SQFT	Temporary Traffic Control Markings
705A030	221	Each	Pavement Markers, Class A-H, Type 2-C
705A032	55	Each	Pavement Markers, Class A-H, Type 1-B
705A037	109	Each	Pavement Markers, Class A-H, Type 2-D
730H001	5,800	LF	Loop Wire
730I001	1,100	LF	Loop Detector Lead-In-Cable
730K000	2	Each	Traffic Signal Junction Box
730L003	200	LF	1", Non-Metallic, Conduit
730L005	60	LF	2", Non-Metallic, Conduit
740B000	956	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740N000	34	Each	Tubular Marker
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit