

**Alabama Department of Transportation
Proposal Item Summary**

026. STPAA-0075(541)

BLOUNT COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 7.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-75 from the junction of Kornegay Road north of Susan Moore to the intersection of SR-74 (US-278) in Snead. Length 6.487 mi.

The Bracket Estimate on this project is from \$1,897,193 to \$2,318,791.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	797	LF	Removing Guardrail
206E008	20	Each	Removing Guardrail End Anchor (All Type)
210D001	225	CUYD	Borrow Excavation (Loose Truckbed Measurement)
401A006	117,176	SQYD	Bituminous Treatment G
405A000	11,760	Gal	Tack Coat
407B000	7	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	117,593	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A356	5,282	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	27	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B002	8,216	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size mix, ESAL Range C/D
424B654	750	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	13	Mile	Scoring Bituminous Pavement Surface
430B043	250	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	775	LF	Steel Beam Guardrail, Class A, Type 2
630C001	1	Each	Guardrail End Anchor, Type 8
630C079	8	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	11	Each	Guardrail End Anchor, Type 20 Series (MASH)
630G006	100	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 6
631C010	238	LF	Guardrail Reset
650A000	90	CUYD	Topsoil
654A001	338	SQYD	Solid Sodding (Bermuda)
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	250	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 102,000.00)
701A227	13	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	307	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	22	Mile	Solid Temporary Traffic Stripe

Item No.	Quantity	Units	Description
701G146	476	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	476	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	951	LF	Solid Traffic Stripe Removed (Tape)
703A002	3,451	SQFT	Traffic Control Markings, Class 2, Type A
703B002	164	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,437	SQFT	Temporary Traffic Control Markings
705A030	23	Each	Pavement Markers, Class A-H, Type 2-C
705A032	479	Each	Pavement Markers, Class A-H, Type 1-B
705A037	998	Each	Pavement Markers, Class A-H, Type 2-D
705A038	166	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,210	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car