

**Alabama Department of Transportation
Proposal Item Summary**

027. STPAA-0117(512)

DEKALB COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 4.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-117 from the junction of SR-7 (US-11) in Hammondville to the junction of SR-40. Length 2.769 mi.

The Bracket Estimate on this project is from \$1,040,339 to \$1,271,525.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	2,950	LF	Removing Guardrail
206E008	10	Each	Removing Guardrail End Anchor (All Type)
405A000	4,003	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	50,026	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	5,308	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	197	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424C364	1,000	Ton	Superpave Bituminous Concrete Base Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	6	Mile	Scoring Bituminous Pavement Surface
430B043	1,422	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
629D003	4	Each	Bridge Guardrail Retrofit, Type SC
630A001	3,175	LF	Steel Beam Guardrail, Class A, Type 2
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	6	Each	Guardrail End Anchor, Type 20 Series (MASH)
665Q002	200	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 61,000.00)
701A227	6	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C001	15	Mile	Solid Temporary Traffic Stripe
701G146	540	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	540	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	1,080	LF	Solid Traffic Stripe Removed (Tape)
703A002	312	SQFT	Traffic Control Markings, Class 2, Type A
703D001	312	SQFT	Temporary Traffic Control Markings
705A037	360	Each	Pavement Markers, Class A-H, Type 2-D
740B000	581	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit