

**Alabama Department of Transportation
Proposal Item Summary**

009. NH-0113(503)

ESCAMBIA COUNTY

Contract Time: 30 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-113 (US-29) from the Florida State Line to the junction of SR-3 (US-31) northeast of Flomaton. Length 0.799 mi.

The Bracket Estimate on this project is from \$432,574 to \$528,701.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	1,186	LF	Removing Guardrail
206E008	8	Each	Removing Guardrail End Anchor (All Type)
405A000	2,242	Gal	Tack Coat
408A052	22,417	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	2,467	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
630A001	1,142	LF	Steel Beam Guardrail, Class A, Type 2
630C001	2	Each	Guardrail End Anchor, Type 8
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
654A001	300	SQYD	Solid Sodding (Bermuda)
665Q002	500	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 23,500.00)
701A227	2	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	2	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	5	Mile	Solid Temporary Traffic Stripe
701G142	1,168	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,168	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,168	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	2,336	LF	Solid Traffic Stripe Removed (Plastic)
701H006	1,168	LF	Broken Traffic Stripe Removed (Plastic)
703A002	1,995	SQFT	Traffic Control Markings, Class 2, Type A
703B002	546	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,767	SQFT	Temporary Traffic Control Markings
703E001	546	SQFT	Temporary Traffic Control Legends
705A030	112	Each	Pavement Markers, Class A-H, Type 2-C
705A032	121	Each	Pavement Markers, Class A-H, Type 1-B
705A037	70	Each	Pavement Markers, Class A-H, Type 2-D
705A038	61	Each	Pavement Markers, Class A-H, Type 2-E
730H001	5,400	LF	Loop Wire
740B000	749	SQFT	Construction Signs
740E000	250	Each	Cones (36 Inches High)
740M001	250	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit