

**Alabama Department of Transportation  
Proposal Item Summary**

**022. STPAA-0022(534)**

**CHILTON COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-22 from the junction of Meadowview Circle to a point west of the intersection of SR-3 (US-31) (MP 66.627) in Clanton. Length 1.727 mi.

The Bracket Estimate on this project is from \$1,071,650 to \$1,309,794.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	9,269	Gal	Tack Coat
408A053	42,504	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	2,869	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	4,251	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	1,047	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
622A004	23	Each	Manhole Covers Reset (Riser Ring Method)
641S500	1	Each	Valve Box Reset
665Q002	400	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 57,500.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B027	125	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B207	3,100	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	14	Mile	Solid Temporary Traffic Stripe
701G146	304	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	288	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	592	LF	Solid Traffic Stripe Removed (Tape)
703A002	1,085	SQFT	Traffic Control Markings, Class 2, Type A
703B002	516	SQFT	Traffic Control Legends, Class 2, Type A
703B011	23	SQFT	Traffic Control Legends, Class W, Type A
703C003	23	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Tape)
703D001	1,284	SQFT	Temporary Traffic Control Markings
705A030	126	Each	Pavement Markers, Class A-H, Type 2-C
705A032	147	Each	Pavement Markers, Class A-H, Type 1-B
705A037	226	Each	Pavement Markers, Class A-H, Type 2-D
705A038	74	Each	Pavement Markers, Class A-H, Type 2-E
707B004	4	Each	Type B Hazard Marker Installation
728A000	2	Each	Truck Mounted Impact Attenuator Unit
740B000	1,173	SQFT	Construction Signs
740C000	27	SQFT	Special Construction Signs
740D000	500	Each	Channelizing Drums
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit

Item No.	Quantity	Units	Description
742A001	2 Each		Portable Changeable Message Sign, Type 2