

**Alabama Department of Transportation  
Proposal Item Summary**

**025. STPAA-NR13(931)**

**MARION AND WINSTON COUNTIES**

Contract Time: 75 Working Days

for constructing the Safety Improvements (Curb Ramp Installations) on SR-253, SR-17, SR-74, SR-142, SR-118, SR-171, SR-13, and SR-195 in the West Central Region (Fayette Area) at various locations as indicated in the plans.

The Bracket Estimate on this project is from \$433,320 to \$529,614.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$20.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C000	816	SQYD	Removing Concrete Sidewalk
206C018	54	SQYD	Removing Asphalt Sidewalk
206D002	208	LF	Removing Curb
206D003	602	LF	Removing Curb And Gutter
206D005	47	LF	Removing Gutter
305B077	50	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	345	Gal	Tack Coat
408A052	3,442	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A360	284	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
517D002	118	LF	Galvanized Steel Sidewalk Handrail
539A000	12	LF	4 Inch Trench Drain
600A000	1	LS	Mobilization
602A000	10	Each	Right Of Way Markers
618A000	279	SQYD	Concrete Sidewalk, 4" Thick
618C001	1,214	SQFT	Detectable Warning Surface
618D000	666	SQYD	Curb Ramp
621C035	1	Each	Inlets, Type B (Surface Grates)
623A000	34	LF	Concrete Gutter
623B000	20	LF	Concrete Curb, Type N
623B002	104	LF	Concrete Curb, Type A
623C000	248	LF	Combination Curb & Gutter, Type C
654A001	83	SQYD	Solid Sodding (Bermuda)
665E000	250	SQYD	Polyethylene
665G000	100	Each	Sand Bags
680A001	1	LS	Geometric Controls
701G265	1,225	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
703A002	6,285	SQFT	Traffic Control Markings, Class 2, Type A
703A011	284	SQFT	Traffic Control Markings, Class W, Type A
703C001	929	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
703D001	1,887	SQFT	Temporary Traffic Control Markings
710A160	18	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B021	28	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
730H001	6,132	LF	Loop Wire
730I001	500	LF	Loop Detector Lead-In-Cable
730K000	2	Each	Traffic Signal Junction Box
730L005	100	LF	2", Non-Metallic, Conduit
740B000	843	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
740E000	50	Each	Cones (36 Inches High)
740F001	16	Each	Barricades, Type II
740M001	50	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit