

**Alabama Department of Transportation  
Proposal Item Summary**

---

**032. STPOA-3521(250)**

**HOUSTON COUNTY**

Contract Time: 30 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-112 (Napier Field Road) from the junction of SR-53 (US-231) in Dothan to the Dale County Line. Length 1.105 mi.

The Bracket Estimate on this project is from \$496,450 to \$606,772.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	1,484	Gal	Tack Coat
408A052	30,940	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A361	3,375	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
665G000	150	Each	Sand Bags
665J002	1,400	LF	Silt Fence
665O001	1,400	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 26,800.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	3	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,179	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	3	Mile	Solid Temporary Traffic Stripe
703A002	2,357	SQFT	Traffic Control Markings, Class 2, Type A
703B002	404	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,357	SQFT	Temporary Traffic Control Markings
703E001	404	SQFT	Temporary Traffic Control Legends
705A030	198	Each	Pavement Markers, Class A-H, Type 2-C
705A037	225	Each	Pavement Markers, Class A-H, Type 2-D
705A038	25	Each	Pavement Markers, Class A-H, Type 2-E
740B000	330	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone