

**Alabama Department of Transportation
Proposal Item Summary**

035. ATRP2-26-2020-026-1

ELMORE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 2.00

for constructing the Safety Improvements (Traffic Signals, Traffic Signs, and Traffic Stripe) on SR-14 at Ingram Road north of Millbrook. Length 0.029 mi.

The Bracket Estimate on this project is from \$68,283 to \$83,457.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
600A000	1	LS	Mobilization
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 3,500.00)
701G249	80	LF	Solid White, Class 2, Type A Traffic Stripe
701G263	280	LF	Solid Yellow, Class 2, Type A Traffic Stripe
703A002	24	SQFT	Traffic Control Markings, Class 2, Type A
705A030	4	Each	Pavement Markers, Class A-H, Type 2-C
710A160	4	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A170	27	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	62	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
710C000	1	LS	Removal Of Existing Roadway Signs
730C030	1	LS	Furnishing And Installing Traffic Control Unit (Temporary)(SR-14 at Ingram Road)
730L002	25	LF	1", Metallic, Conduit
730L003	30	LF	1", Non-Metallic, Conduit
730L005	85	LF	2", Non-Metallic, Conduit
730P022	6	Each	Vehicular Signal Head, 12 Inch, 3 Section, Type LED
730R022	1	Each	Controller Assembly, Type III, 8 Phase
730T000	4	Each	Wood Pole
730U015	1	LS	Video Detection System (SR-14 at Ingram Road)
740B000	416	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone