

**Alabama Department of Transportation
Proposal Item Summary**

014. HSIP-0165(506)

RUSSELL COUNTY

Contract Time: 45 Working Days

for constructing the Additional Turn Lane (Grading, Drainage, Pavement, and Bridge Culvert Extension) on SR-165 at the junction of CR-24 south of Fort Mitchell. Length 0.225 mi.

The Bracket Estimate on this project is from \$691,589 to \$845,276.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
206D000	72	LF	Removing Pipe
206E000	2	Each	Removing Headwalls
209A000	1	Each	Mailbox Reset, Single
210A000	725	CUYD	Unclassified Excavation
210D021	923	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	95	CUYD	Structure Excavation
214B001	60	CUYD	Foundation Backfill, Commercial
305B077	750	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	565	Gal	Tack Coat
408B001	3,100	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
424A356	300	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	275	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B693	700	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
430B043	30	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	9,141	LB	Steel Reinforcement
505I000	1,200	SQFT	Temporary Steel Sheet Piling
524B011	75	CUYD	Culvert Concrete Extension (Cast In Place)
530A000	24	LF	15" Roadway Pipe (Class 3 R.C.)
535A002	80	LF	24" Side Drain Pipe
600A000	1	LS	Mobilization
610C001	2,035	Ton	Loose Riprap, Class 2
610D003	2,150	SQYD	Filter Blanket, Geotextile
619A003	4	Each	24" Roadway Pipe End Treatment, Class 1
620A000	1	CUYD	Minor Structure Concrete
630A034	363	LF	Steel Beam Guardrail, Class A, Type 2 (8'-0" Post)
630C080	4	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	100	CUYD	Topsoil
652A100	1	Acre	Seeding
652C000	1	Acre	Mowing
654A001	40	SQYD	Solid Sodding (Bermuda)
656A010	1	Acre	Mulching
659C002	1,500	SQYD	Erosion Control Product, Type S2

Item No.	Quantity	Units	Description
665A000	3	Acre	Temporary Seeding
665B001	9	Ton	Temporary Mulching
665G000	50	Each	Sand Bags
665J002	1,200	LF	Silt Fence
665N000	100	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	1,200	LF	Silt Fence Removal
665Q002	350	LF	Wattle
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 35,570.00)
701B207	200	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	3	Mile	Solid Temporary Traffic Stripe
701G253	2,424	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G265	3,916	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
703A002	638	SQFT	Traffic Control Markings, Class 2, Type A
703B002	45	SQFT	Traffic Control Legends, Class 2, Type A
703D001	166	SQFT	Temporary Traffic Control Markings
705A030	15	Each	Pavement Markers, Class A-H, Type 2-C
705A032	466	Each	Pavement Markers, Class A-H, Type 1-B
705A037	10	Each	Pavement Markers, Class A-H, Type 2-D
705A038	233	Each	Pavement Markers, Class A-H, Type 2-E
707B004	40	Each	Type B Hazard Marker Installation
711A000	1	LS	Roadway Sign Relocation
740B000	566	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone