

**Alabama Department of Transportation
Proposal Item Summary**

021. STPBH-0003(619)

JEFFERSON COUNTY

Contract Time: 160 Working Days

DBE Goal Percent: 1.00

for constructing the Roadway Lighting on SR-3 (US-31) from the Patton Chapel Road Intersection to the I-65 Interchange in Hoover. Length 1.343 mi.

The Bracket Estimate on this project is from \$1,271,595 to \$1,554,172.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$17.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
600A000	1	LS	Mobilization
654A001	200	SQYD	Solid Sodding (Bermuda)
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665G000	330	Each	Sand Bags
665J002	2,340	LF	Silt Fence
665O001	2,340	LF	Silt Fence Removal
665Q002	1,500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 40,760.00)
740B000	956	SQFT	Construction Signs
740D000	150	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2
750B602	53	Each	Roadway Luminaire Assembly with One, LED, 400 Watt Equivalent Luminaire
750C010	53	Each	Pole Foundation,Roadway
750D200	80	Each	Electrical Junction Box,Type 1
750E113	140	LF	Conduit, 1 1/4 Inch, Rigid Nonmetallic
750F026	560	LF	Conductor, #2 AWG
750G022	3,602	LF	Combined Duct And Cable, 4 #4 AWG/ 1 #6 AWG GND
750G032	4,725	LF	Combined Duct and Cable, 4 #2 AWG/ 1 #6 AWG GND
750G034	5,203	LF	Combined Duct and Cable, 6 #2 AWG/ 1 #6 AWG GND
750H005	2	Each	Service Pole
750I015	2	Each	Lighting Control Center
751J006	8	Each	Remove Luminaire Pole Foundation, Concrete
751L002	2	Each	Remove Lighting Control Center, 6 Circuit
751L025	84	Each	Remove Roadway Luminaire Assembly
751M000	1	LS	Remove Conductors
756A022	5,810	LF	4" Electrical Conduit, 1 Line, Type 5 Installation