

**Alabama Department of Transportation
Proposal Item Summary**

028. STPNU-5318(251)

PERRY COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 2.00

for constructing the Planing, Resurfacing, Full Depth Reclamation, Guardrail Replacement, and Traffic Stripe on CR-12 from the East City Limits of Uniontown to the junction of SR-5. Length 6.909 mi.

The Bracket Estimate on this project is from \$2,320,940 to \$2,836,704.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	1,225	LF	Removing Guardrail
206E019	48	Each	Removing Guardrail End Anchor (Type 10)
210D021	600	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	316	STA	Machine Grading Shoulders
302A000	93,669	SQYD	Full Depth Reclamation, 10 Inches Thick
302B000	2,951	Ton	Portland Cement For Full Depth Reclamation
401A000	89,411	SQYD	Bituminous Treatment A
401B108	89,411	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	7,153	Gal	Tack Coat
408A053	10,026	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
408A054	4,886	SQYD	Planing Existing Pavement (Approximately 3.10" Thru 4.0" Thick)
408A055	10,237	SQYD	Planing Existing Pavement (Approximately 4.10" Thru 5.0" Thick)
408A056	2,497	SQYD	Planing Existing Pavement (Approximately 5.10" Thru 6.0" Thick)
424A340	5,748	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,703	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	3,510	SQYD	Filter Blanket, Geotextile
630A001	725	LF	Steel Beam Guardrail, Class A, Type 2
630C080	48	Each	Guardrail End Anchor, Type 20 Series (MASH)
630G003	438	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 3
630G004	75	LF	Steel Beam Guardrail for Culvert, Class A, Type 2, Case 4
652A100	5	Acre	Seeding
656A010	5	Acre	Mulching
665J002	1,500	LF	Silt Fence
665O001	1,500	LF	Silt Fence Removal
665Q002	1,500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 121,097.55)
701C000	15	Mile	Broken Temporary Traffic Stripe
701C001	15	Mile	Solid Temporary Traffic Stripe
703A004	366	SQFT	Traffic Control Markings, Class 2T, Type A
740B000	567	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car