

**Alabama Department of Transportation
Proposal Item Summary**

033. STPOA-8822(601)

COLBERT COUNTY

Contract Time: 110 Working Days

DBE Goal Percent: 7.00

for constructing the Micro-Milling, Resurfacing, Drainage Improvements, Sidewalk Installation, and Traffic Stripe on Cox Boulevard from the junction of Avalon Avenue to the junction of SR-184 (East Second Street) in Sheffield. Length 1.116 mi.

The Bracket Estimate on this project is from \$2,142,739 to \$2,618,903.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$31.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
206C010	1,043	SQYD	Removing Concrete Driveway
206D003	499	LF	Removing Curb And Gutter
206D005	301	LF	Removing Gutter
210A000	2,957	CUYD	Unclassified Excavation
210D001	3,534	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	310	CUYD	Structure Excavation
214B001	94	CUYD	Foundation Backfill, Commercial
301A012	300	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
305B077	500	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	4,250	Gal	Tack Coat
408B001	30,000	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
424A360	2,500	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	3,000	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	1,110	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B689	6,287	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	500	Ton	Aggregate Surfacing (1" Down, Crusher Run)
530A100	10	LF	15" Roadway Pipe (Class 3 R.C.) (Extension)
530B002	98	LF	29" Span, 18" Rise Roadway Pipe (Class 3 R.C.)
530B005	150	LF	51" Span, 31" Rise Roadway Pipe (Class 3 R.C.)
535B090	254	LF	18" Span, 11" Rise Side Drain Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
602A000	34	Each	Right Of Way Markers
610C001	74	Ton	Loose Riprap, Class 2
610D003	850	SQYD	Filter Blanket, Geotextile
614A000	110	CUYD	Slope Paving
618A000	2,649	SQYD	Concrete Sidewalk, 4" Thick
618B003	819	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
619A001	2	Each	15" Roadway Pipe End Treatment, Class 1
619A002	2	Each	18" Roadway Pipe End Treatment, Class 1
619B115	10	Each	18" Span, 11" Rise Side Drain Pipe End Treatment, Class 1
619B267	2	Each	29" Span, 18" Rise Roadway Pipe End Treatment, Class 1 (Double Line)
619B285	2	Each	51" Span, 31" Rise Roadway Pipe End Treatment, Class 2 (Double Line)
620A000	1	CUYD	Minor Structure Concrete
621C109	1	Each	Inlets, Type PD

Item No.	Quantity	Units	Description
623A001	342	LF	Concrete Gutter (Valley)
623A004	149	LF	Concrete Gutter (Modified)
623C000	719	LF	Combination Curb & Gutter, Type C
637A000	94	LF	Fence Reset
650A000	1,349	CUYD	Topsoil
652A100	3	Acre	Seeding
654A001	12,148	SQYD	Solid Sodding (Bermuda)
656A010	3	Acre	Mulching
665A000	3	Acre	Temporary Seeding
665B001	9	Ton	Temporary Mulching
665E000	250	SQYD	Polyethylene
665F000	250	Each	Hay Bales
665G000	400	Each	Sand Bags
665J002	3,600	LF	Silt Fence
665N000	80	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	3,600	LF	Silt Fence Removal
665P005	3	Each	Inlet Protection, Stage 3 Or 4
665Q002	860	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 111,955.00)
701A227	3	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	891	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	3	Mile	Solid Temporary Traffic Stripe
703A002	4,036	SQFT	Traffic Control Markings, Class 2, Type A
703B002	225	SQFT	Traffic Control Legends, Class 2, Type A
703D001	39	SQFT	Temporary Traffic Control Markings
705A030	41	Each	Pavement Markers, Class A-H, Type 2-C
705A032	178	Each	Pavement Markers, Class A-H, Type 1-B
705A037	217	Each	Pavement Markers, Class A-H, Type 2-D
705A038	89	Each	Pavement Markers, Class A-H, Type 2-E
710A160	59	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A165	15	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710A170	89	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	392	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
711A000	1	LS	Roadway Sign Relocation
740B000	850	SQFT	Construction Signs
740D000	250	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740F002	8	Each	Barricades, Type III
740I002	3	Each	Warning Lights, Type B
740M001	50	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2