

**Alabama Department of Transportation
Proposal Item Summary**

037. ATRP2-36-2020-525

JACKSON COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 4.00

for constructing the Acceleration Lane on SR-2 (US-72) at the junction of SR-35 in Woodville. Length 0.165 mi.

The Bracket Estimate on this project is from \$240,664 to \$294,145.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$13.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210A000	104	CUYD	Unclassified Excavation
210D001	448	CUYD	Borrow Excavation (Loose Truckbed Measurement)
405A000	277	Gal	Tack Coat
408A053	1,044	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410H000	1	Each	Material Remixing Device
424A340	76	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	92	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B666	666	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
610D003	100	SQYD	Filter Blanket, Geotextile
650A000	776	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665I000	3	Ton	Temporary Riprap, Class 2
665J002	1,200	LF	Silt Fence
665O001	1,200	LF	Silt Fence Removal
665P005	4	Each	Inlet Protection, Stage 3 Or 4
665Q002	100	LF	Wattle
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 11,865.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	300	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	1	Mile	Solid Temporary Traffic Stripe
703A002	459	SQFT	Traffic Control Markings, Class 2, Type A
703B002	90	SQFT	Traffic Control Legends, Class 2, Type A
705A030	40	Each	Pavement Markers, Class A-H, Type 2-C
710A170	24	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	24	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	491	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740F002	2	Each	Barricades, Type III
740M001	50	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit