

**Alabama Department of Transportation
Proposal Item Summary**

010. BR-0117(506)

JACKSON COUNTY

Contract Time: 380 Working Days

for constructing the Bridge Rehabilitation and Bridge Painting on SR-117 over the Tennessee River and the Tennessee River Relief Bridge southeast of Stevenson. Length 0.435 mi.

The Bracket Estimate on this project is from \$6,138,131 to \$7,502,160.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$30.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206A050	1	LS	Removal Of Old Bridge, Partial, Station 100+00.00
206A051	1	LS	Removal Of Old Bridge, Partial, Station 100+00.00
206A052	1	LS	Removal Of Old Bridge, Partial, Station 100+00.00
206A053	1	LS	Removal Of Old Bridge, Partial, Station 100+00.00
206C012	25	SQYD	Removing Bridge Deck (Partial Only)
490A000	4,047	SQYD	Blast Cleaning
490B003	4,047	SQYD	Bridge Deck Overlay
490D000	255	SQFT	Bridge Deck Spall Repair
502A001	306	LB	Steel Reinforcement (Grade 60)
508A000	109,717	LB	Structural Steel
508C000	2	Set	Bearing Plates Bronze (One Set Consists Of Plates) Bronze
510A007	6	CUYD	Bridge Substructure Concrete
510B001	12	CUYD	Bridge Concrete, Class A
511A000	28	Each	Elastomeric Bearing Type 1
520A100	1	LS	Repairs to Existing Bridge, Station 100+00.00
520A101	1	LS	Repairs to Existing Bridge, Station 100+00.00
520A102	1	LS	Repairs to Existing Bridge, Station 100+00.00
520A103	1	LS	Repairs to Existing Bridge, Station 100+00.00
520A104	1	LS	Repairs to Existing Bridge, Station 100+00.00
520C000	1	LS	Raising Portion Of Existing Bridge , Station 100+00.00
521B000	1	LS	Coating Existing Bridge At Station 82+10.33
521B001	1	LS	Coating Existing Bridge At Station 100+00.00
522G000	81	LF	Bridge Joint Seal
600A000	1	LS	Mobilization
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 205,000.00)
701A091	1	Mile	Solid White, Class W, Type A Traffic Stripe (5" Wide)
701A099	1	Mile	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701C005	3	Mile	Solid Temporary Traffic Stripe (Tape)
701C006	3	Mile	Solid Temporary Traffic Stripe (Removable Tape)
726A000	2,570	LF	Portable Concrete Safety Barriers, Type 6
726A001	40	LF	Portable Concrete Safety Barriers, Type 6-A
726D025	4	Each	Portable Impact Attenuator Assembly (Unidirectional,TL-3)
740B000	438	SQFT	Construction Signs
740C000	32	SQFT	Special Construction Signs
740D000	26	Each	Channelizing Drums
740E000	14	Each	Cones (36 Inches High)
740F002	2	Each	Barricades, Type III
740M001	14	Each	Ballast For Cone

Item No.	Quantity	Units	Description
740P000	1	LS	Portable Rumble Strip
757A011	2	Each	Portable Traffic Signal, Type TR1