

**Alabama Department of Transportation
Proposal Item Summary**

015. HRRR-4121(250)

LEE COUNTY

Contract Time: 20 Working Days

for constructing the Safety Improvements (Planing, Superelevation Corrections, Shoulder Widening, Traffic Stripe, Centerline Scoring, and Pavement Markers) on CR-179 from the Little Uchee Creek Bridge to a point 1329 feet north southwest of Smiths Station. Length 0.251 mi.

The Bracket Estimate on this project is from \$193,441 to \$236,428.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210D021	443	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
405A000	682	Gal	Tack Coat
408A052	366	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A340	293	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	375	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B673	496	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424C350	163	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	1	Mile	Scoring Bituminous Pavement Surface
430B043	54	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 10,000.00)
701A231	1	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701C001	2	Mile	Solid Temporary Traffic Stripe
705A037	96	Each	Pavement Markers, Class A-H, Type 2-D
740B000	235	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III