

**Alabama Department of Transportation
Proposal Item Summary**

019. HSIP-0001(618)

HOUSTON COUNTY

Contract Time: 30 Working Days

for constructing the Left Turn Lane Addition and Intersection Modifications on SR-1 (US-431) at Grey Hodges Road in Dothan. Length 0.405 mi.

The Bracket Estimate on this project is from \$286,415 to \$350,062.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D000	60	LF	Removing Pipe
210A000	100	CUYD	Unclassified Excavation
210D021	400	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
230A000	7	RBST	Roadbed Processing
301A025	1,428	SQYD	Crushed Aggregate Base Course, Type B, Road Mixed, 6" Compacted Thickness
401A000	1,350	SQYD	Bituminous Treatment A
405A000	260	Gal	Tack Coat
410H000	1	Each	Material Remixing Device
424A370	108	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	108	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	163	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
530B002	200	LF	29" Span, 18" Rise Roadway Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
614A000	25	CUYD	Slope Paving
619B142	4	Each	29" Span, 18" Rise Side Drain Pipe End Treatment, Class 2
654A001	950	SQYD	Solid Sodding (Bermuda)
665G000	200	Each	Sand Bags
665P005	2	Each	Inlet Protection, Stage 3 Or 4
665Q002	600	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 16,000.00)
701A227	1	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	428	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	1	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	125	SQFT	Traffic Control Markings, Class 2, Type A
703B002	90	SQFT	Traffic Control Legends, Class 2, Type A
705A030	21	Each	Pavement Markers, Class A-H, Type 2-C
710A160	117	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)

Item No.	Quantity	Units	Description
710B021	210	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2 ", 14 Ga Square Tubular Steel)
728A000	1	Each	Truck Mounted Impact Attenuator Unit
740B000	1,115	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2