

**Alabama Department of Transportation
Proposal Item Summary**

036. STPMN-0120(251)

AUTAUGA COUNTY

Contract Time: 30 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on CR-10 from the junction of SR-6 (US-82) to the junction of CR-57 northwest of Prattville. Length 4.573 mi.

The Bracket Estimate on this project is from \$453,721 to \$554,548.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	5,292	Gal	Tack Coat
408A052	4,238	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A346	3,981	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
650A000	157	CUYD	Topsoil
652A100	5	Acre	Seeding
656A010	5	Acre	Mulching
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 23,000.00)
701A030	9	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	6	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	3	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	15	Mile	Solid Temporary Traffic Stripe
703A004	456	SQFT	Traffic Control Markings, Class 2T, Type A
703B004	137	SQFT	Traffic Control Legends, Class 2T, Type A
705A032	124	Each	Pavement Markers, Class A-H, Type 1-B
705A037	431	Each	Pavement Markers, Class A-H, Type 2-D
740B000	435	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car