

**Alabama Department of Transportation
Proposal Item Summary**

043. ATRP2-52-2020-176

MORGAN COUNTY

Contract Time: 115 Working Days

DBE Goal Percent: 5.00

for constructing the Intersection Improvements (Grading, Drainage, Pavement, Traffic Signal Modifications, and Traffic Stripe) on SR-67 (Beltline Road) at Sandlin Road and Central Parkway in Decatur. Length 0.374 mi.

The Bracket Estimate on this project is from \$1,574,343 to \$1,924,197.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$32.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C002	1,766	SQYD	Removing Concrete Slope Paving
206D000	51	LF	Removing Pipe
206E001	4	Each	Removing Inlets
210A000	5,995	CUYD	Unclassified Excavation
210D001	100	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	838	CUYD	Structure Excavation
214B001	297	CUYD	Foundation Backfill, Commercial
305B071	654	Ton	Coarse Aggregate, Section 801, For Miscellaneous Use
327A021	702	Ton	Plant Mix Bituminous Base, Mix 2
405A000	1,568	Gal	Tack Coat
408B001	1,409	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
424A360	357	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	271	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	243	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B681	782	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B014	50	Ton	Aggregate Surfacing (ALDOT #410 Modified)
430B040	1,115	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type B)
430B046	50	Ton	Aggregate Surfacing (Aldot #2)
430B050	1,277	Ton	Aggregate Surfacing(ALDOT#1)
530A001	16	LF	18" Roadway Pipe (Class 3 R.C.)
530B001	48	LF	22" Span, 14" Rise Roadway Pipe (Class 3 R.C.)
532A040	584	LF	12" Slotted Drain Pipe (With Variable Height Grate)
532A041	247	LF	15" Slotted Drain Pipe (With Variable Height Grate)
533A098	241	LF	18" Storm Sewer Pipe (Class 3 R.C.)
533B097	221	LF	18" Span, 11" Rise Storm Sewer Pipe (Class 3 R.C.)
533B098	515	LF	22" Span, 14" Rise Storm Sewer Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
608A000	1,491	SQYD	Separation Geotextile
610C000	2,061	Ton	Loose Riprap, Class 1
610D003	96	SQYD	Filter Blanket, Geotextile
614A000	292	CUYD	Slope Paving
621A011	11	Each	Junction Boxes, Type 1 Or 1P
621C001	10	Each	Inlets, Type B
621C008	3	Each	Inlets, Type E
621C020	1	Each	Inlets, Type Y
621D008	3	Each	Inlet Units, Type E

Item No.	Quantity	Units	Description
650A000	195	CUYD	Topsoil
654A006	1,771	SQYD	Solid Sodding (Myers Zoysia)
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665E000	500	SQYD	Polyethylene
665G000	50	Each	Sand Bags
665P005	23	Each	Inlet Protection, Stage 3 Or 4
665Q002	704	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 84,000.00)
701B207	688	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	1	Mile	Solid Temporary Traffic Stripe
701G265	1,867	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
703A002	3,642	SQFT	Traffic Control Markings, Class 2, Type A
703B002	180	SQFT	Traffic Control Legends, Class 2, Type A
703D001	319	SQFT	Temporary Traffic Control Markings
705A030	88	Each	Pavement Markers, Class A-H, Type 2-C
730A060	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-67 (Beltline Road) at Central Parkway)
730A061	1	LS	Removal Of Existing Traffic Control Unit (Partial) (SR-67 (Beltline Road) at Sandlin Road)
730C000	1	LS	Furnishing And Installing Traffic Control Unit (SR-67 (Beltline Road) at Central Parkway)
730C001	1	LS	Furnishing And Installing Traffic Control Unit (SR-67 (Beltline Road) at Sandlin Road)
730P023	4	Each	Vehicular Signal Head, 12 Inch, 4 Section, Type LED
740B000	1,030	SQFT	Construction Signs
740D000	250	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740F002	16	Each	Barricades, Type III
740M001	100	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2