

**Alabama Department of Transportation
Proposal Item Summary**

009. IM-1020(361)

CLEBURNE COUNTY

Contract Time: 55 Working Days

DBE Goal Percent: 1.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on I-20 from the SR-46 Interchange (Exit 205) to the CR-49 Interchange (Exit 210). Length 5.858 mi.

The Bracket Estimate on this project is from \$3,044,167 to \$3,720,649.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	200	Gal	Tack Coat
408B000	277,270	SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
408B001	5,867	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	14,884	Ton	Polymer Modified Open Graded Friction Course
420B000	15,618	Gal	Open Graded Friction Course Tack Coat
424B285	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
424B287	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
432A000	160,382	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 179,000.00)
701A227	12	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	24	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	5,932	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	48	Mile	Broken Temporary Traffic Stripe
701C001	48	Mile	Solid Temporary Traffic Stripe
701E003	3,456	LF	Solid Temporary Traffic Stripe (Tape)
701E013	3,456	LF	Broken Temporary Traffic Stripe (Tape)
701G142	3,456	LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,728	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,728	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G161	2,400	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
701H002	3,456	LF	Solid Traffic Stripe Removed (Tape)
701H007	3,456	LF	Broken Traffic Stripe Removed (Tape)
703A002	3,413	SQFT	Traffic Control Markings, Class 2, Type A
703B002	140	SQFT	Traffic Control Legends, Class 2, Type A
705A030	1,547	Each	Pavement Markers, Class A-H, Type 2-C
705A031	1,342	Each	Pavement Markers, Class A-H, Type 1-A
705A032	214	Each	Pavement Markers, Class A-H, Type 1-B
740B000	2,150	SQFT	Construction Signs
740C000	48	SQFT	Special Construction Signs
740D000	400	Each	Channelizing Drums
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2