

**Alabama Department of Transportation
Proposal Item Summary**

013. NH-0012(575)

CHOCTAW COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 1.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-12 (US-84) from the intersection of SR-17 to 1.600 miles east of the junction of CR-6 (Bladon Springs Road) east of Bolinger. Length 7.575 mi.

The Bracket Estimate on this project is from \$1,733,262 to \$2,118,431.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	6,500	Gal	Tack Coat
408A052	145,187	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	9,601	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	250	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	1,053	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	16	Mile	Scoring Bituminous Pavement Surface
430B043	150	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	115,560	SQYD	Scrub Seal
600A000	1	LS	Mobilization
650A000	100	CUYD	Topsoil
652A100	9	Acre	Seeding
652C000	28	Acre	Mowing
656A010	9	Acre	Mulching
665Q002	300	LF	Wattle
666A001	9	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 59,200.00)
701A227	16	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	28	Mile	Broken Temporary Traffic Stripe
701C001	87	Mile	Solid Temporary Traffic Stripe
701G146	476	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	238	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	238	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	714	LF	Solid Traffic Stripe Removed (Tape)
701H007	238	LF	Broken Traffic Stripe Removed (Tape)
703A002	328	SQFT	Traffic Control Markings, Class 2, Type A
703B002	56	SQFT	Traffic Control Legends, Class 2, Type A
703D001	328	SQFT	Temporary Traffic Control Markings
703E001	56	SQFT	Temporary Traffic Control Legends
705A032	308	Each	Pavement Markers, Class A-H, Type 1-B
705A037	559	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,496	SQFT	Construction Signs
740E000	100	Each	Cones (36 Inches High)

Item No.	Quantity	Units	Description
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car