

**Alabama Department of Transportation
Proposal Item Summary**

016. NH-0077(526)

TALLADEGA COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 4.00

for constructing the Micro-Milling, Guardrail Installation, Resurfacing, and Traffic Stripe on SR-77 from the junction of CR-414 to the I-20 Overpass (MP 75.941) in Lincoln. Length 1.649 mi.

The Bracket Estimate on this project is from \$854,690 to \$1,044,622.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	385	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
401B100	59,128	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	1,774	Gal	Tack Coat
408B001	59,128	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	4,287	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	150	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	9	Mile	Scoring Bituminous Pavement Surface
430B043	200	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	385	LF	Steel Beam Guardrail, Class A, Type 2
630C079	2	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 50,000.00)
701A227	4	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	4	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	3,150	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	12	Mile	Broken Temporary Traffic Stripe
701C001	22	Mile	Solid Temporary Traffic Stripe
703A002	5,400	SQFT	Traffic Control Markings, Class 2, Type A
703B002	247	SQFT	Traffic Control Legends, Class 2, Type A
703D001	504	SQFT	Temporary Traffic Control Markings
705A030	254	Each	Pavement Markers, Class A-H, Type 2-C
705A032	415	Each	Pavement Markers, Class A-H, Type 1-B
705A037	112	Each	Pavement Markers, Class A-H, Type 2-D
705A038	196	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,272	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit

Item No.	Quantity	Units	Description
742A001	2 Each		Portable Changeable Message Sign, Type 2