

**Alabama Department of Transportation
Proposal Item Summary**

020. RASTPNU-4017(251)

LAWRENCE COUNTY

Contract Time: 70 Working Days

DBE Goal Percent: 2.00

for constructing the Roadway Improvements (Realignment) on CR-434 from the junction of CR-429 southeast of Hillsboro to approximately 900 feet north of the proposed at-grade. Length 0.507 mi.

The Bracket Estimate on this project is from \$657,167 to \$803,204.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201C000	1	LS	Clearing
206D000	50	LF	Removing Pipe
210A000	882	CUYD	Unclassified Excavation
210D001	468	CUYD	Borrow Excavation (Loose Truckbed Measurement)
210D021	2,791	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	224	CUYD	Structure Excavation
214B001	336	CUYD	Foundation Backfill, Commercial
230A000	28	RBST	Roadbed Processing
243A033	2,278	SQYD	Geosynthetic Reinforcement For Soft Soil Stabilization, Type 1
301A012	10,442	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	6,319	SQYD	Bituminous Treatment A
405A000	206	Gal	Tack Coat
424A340	541	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	919	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	407	Ton	Aggregate Surfacing (1" Down, Crusher Run)
430B046	67	Ton	Aggregate Surfacing (Aldot #2)
530A002	122	LF	24" Roadway Pipe (Class 3 R.C.)
530A258	60	LF	48" Roadway Pipe (14 Gauge C.C.M.P.I.) (Extension)
530A303	156	LF	30" Roadway Pipe (14 Gauge C.M.)
600A000	1	LS	Mobilization
610C001	95	Ton	Loose Riprap, Class 2
610D003	239	SQYD	Filter Blanket, Geotextile
619A003	4	Each	24" Roadway Pipe End Treatment, Class 1
620A000	10	CUYD	Minor Structure Concrete
650A000	426	CUYD	Topsoil
652A100	3	Acre	Seeding
656A010	3	Acre	Mulching
665A000	9	Acre	Temporary Seeding
665B001	6	Ton	Temporary Mulching
665I000	25	Ton	Temporary Riprap, Class 2
665J002	3,500	LF	Silt Fence
665O001	3,500	LF	Silt Fence Removal
665Q002	40	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 33,500.00)
701A231	2	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe

Item No.	Quantity	Units	Description
701G251	275	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	132	SQFT	Traffic Control Markings, Class 2, Type A
703B002	137	SQFT	Traffic Control Legends, Class 2, Type A
705A032	4	Each	Pavement Markers, Class A-H, Type 1-B
705A037	34	Each	Pavement Markers, Class A-H, Type 2-D
710A160	15	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710A165	15	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710A170	32	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)
710B021	120	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	170	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B