

**Alabama Department of Transportation
Proposal Item Summary**

032. STPAA-HSIP-0014(551)

GREENE COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Micro-Milling, Resurfacing, and Traffic Stripe on SR-14 from the junction of SR-13 to the Hale County Line. Length 4.467 mi.

The Bracket Estimate on this project is from \$2,017,635 to \$2,465,998.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	2,113	LF	Removing Guardrail
206E008	30	Each	Removing Guardrail End Anchor (All Type)
305B077	271	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	12,670	Gal	Tack Coat
408B001	55,089	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A356	3,427	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	35	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B002	3,820	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size mix, ESAL Range C/D
424B685	1,472	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B687	475	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	1,363	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	7	Mile	Scoring Bituminous Pavement Surface
430B050	4,886	Ton	Aggregate Surfacing(ALDOT#1)
433A000	48,918	SQYD	Scrub Seal
600A000	1	LS	Mobilization
630A001	2,375	LF	Steel Beam Guardrail, Class A, Type 2
630C079	16	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	14	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	400	LF	Guardrail Reset
665J002	330	LF	Silt Fence
665O001	330	LF	Silt Fence Removal
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 117,000.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	75	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	10	Mile	Broken Temporary Traffic Stripe
701C001	53	Mile	Solid Temporary Traffic Stripe
701G146	9,164	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	2,790	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	5,480	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701H002	14,654	LF	Solid Traffic Stripe Removed (Tape)
701H007	2,790	LF	Broken Traffic Stripe Removed (Tape)
703A002	789	SQFT	Traffic Control Markings, Class 2, Type A
703B002	23	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,573	SQFT	Temporary Traffic Control Markings
705A030	6	Each	Pavement Markers, Class A-H, Type 2-C
705A032	172	Each	Pavement Markers, Class A-H, Type 1-B
705A037	330	Each	Pavement Markers, Class A-H, Type 2-D
705A038	31	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,364	SQFT	Construction Signs
740D000	120	Each	Channelizing Drums
740O000	1	Each	Pilot Car
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit