

**Alabama Department of Transportation
Proposal Item Summary**

001. ERPR-9070(932)

WILCOX COUNTY

Contract Time: 30 Working Days

for constructing the Slide Repair on CR-37 at various sites between the intersection of CR-31 and the junction of CR-43 northeast of Camden. Length 0.084 mi.

The Bracket Estimate on this project is from \$543,537 to \$664,323.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
206D001	163	LF	Removing Guardrail
206D028	1,400	LF	Removing Steel Sheet Piling
206E000	1	Each	Removing Headwalls
206E008	4	Each	Removing Guardrail End Anchor (All Type)
210A000	1,200	CUYD	Unclassified Excavation
210D020	2,720	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A2 or Better)
214A000	132	CUYD	Structure Excavation
214B001	198	CUYD	Foundation Backfill, Commercial
430B003	335	Ton	Aggregate Surfacing (ALDOT #57)
505E000	1,875	LF	Permanent Steel Sheet Piling
530A236	35	LF	108" Roadway Pipe (10 Gauge C.C.S.P.I.) (Extension)
600A000	1	LS	Mobilization
602A000	2	Each	Right Of Way Markers
610C001	115	Ton	Loose Riprap, Class 2
610D003	1,000	SQYD	Filter Blanket, Geotextile
630A001	100	LF	Steel Beam Guardrail, Class A, Type 2
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
650A000	200	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665B001	3	Ton	Temporary Mulching
665E000	265	SQYD	Polyethylene
665F000	100	Each	Hay Bales
665G000	200	Each	Sand Bags
665J002	350	LF	Silt Fence
665O001	350	LF	Silt Fence Removal
665Q002	50	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 44,200.00)
740B000	387	SQFT	Construction Signs
740E000	50	Each	Cones (36 Inches High)
740F002	8	Each	Barricades, Type III
740M001	50	Each	Ballast For Cone