

**Alabama Department of Transportation
Proposal Item Summary**

004. HRRR-0521(250)

BLOUNT COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Widening, Resurfacing, and Traffic Stripe on CR-8 (Skyline Drive) from the junction of Rickwood Caverns Road to a point easterly at MP 4.355 west of Smoke Rise. Length 2.140 mi.

The Bracket Estimate on this project is from \$234,292 to \$286,357.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201C000	1	LS	Clearing
206C010	45	SQYD	Removing Concrete Driveway
206E043	278	Each	Removing Raised Pavement Markers
209A000	3	Each	Mailbox Reset, Single
305B071	25	Ton	Coarse Aggregate, Section 801, For Miscellaneous Use
327D021	1,100	Ton	Plant Mix Bituminous Base, Widening, Mix 2
403B000	250	Ton	Micro-Surfacing Seal Coat, Type II
405A000	200	Gal	Tack Coat
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 12,000.00)
701A231	5	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701C001	5	Mile	Solid Temporary Traffic Stripe
703A002	254	SQFT	Traffic Control Markings, Class 2, Type A
705A031	139	Each	Pavement Markers, Class A-H, Type 1-A
705A037	283	Each	Pavement Markers, Class A-H, Type 2-D
710A165	508	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background, Fluorescent)
710B021	456	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	331	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car