

**Alabama Department of Transportation
Proposal Item Summary**

006. HRRR-4521(250)

MADISON COUNTY

Contract Time: 30 Working Days

for constructing the Safety Improvements (Shoulder Widening, Guardrail Installation, Pavement Markers, and Traffic Stripe) on Dug Hill Road from a point 1500 feet north of the junction of King Drake Road to the junction of Raintree Road in Huntsville. Length 0.109 mi.

The Bracket Estimate on this project is from \$92,950 to \$113,606.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210D001	147	CUYD	Borrow Excavation (Loose Truckbed Measurement)
430B043	32	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610C001	660	Ton	Loose Riprap, Class 2
610D003	500	SQYD	Filter Blanket, Geotextile
630A034	450	LF	Steel Beam Guardrail, Class A, Type 2 (8'-0" Post)
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
665J002	625	LF	Silt Fence
665O001	625	LF	Silt Fence Removal
701G253	1,154	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G265	1,154	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
705A031	48	Each	Pavement Markers, Class A-H, Type 1-A
705A037	24	Each	Pavement Markers, Class A-H, Type 2-D
740B000	177	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740M001	25	Each	Ballast For Cone
740O000	1	Each	Pilot Car