

**Alabama Department of Transportation  
Proposal Item Summary**

**023. RP-NH-FMGR-0005(562) & NH-0005(564)**

**DALLAS COUNTY**

Contract Time: 70 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, Guardrail Installation, Steel Blockout Replacement, and Traffic Stripe on SR-5 from the intersection of CR-21 to the Perry County Line. Length 7.822 mi.

The Bracket Estimate on this project is from \$2,567,491 to \$3,138,044.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	4,013	LF	Removing Guardrail
206E008	28	Each	Removing Guardrail End Anchor (All Type)
401B101	76,000	SQYD	Bituminous Treatment F (With Polymer Additive)
405A000	8,200	Gal	Tack Coat
408A052	66,925	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	10,300	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	179	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B656	1,480	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	3,500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B659	4,200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	15	Mile	Scoring Bituminous Pavement Surface
430B043	1,860	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	600	SQYD	Filter Blanket, Geotextile
630A001	3,863	LF	Steel Beam Guardrail, Class A, Type 2
630C003	16	Each	Guardrail End Anchor, Type 13
630C080	12	Each	Guardrail End Anchor, Type 20 Series (MASH)
665G000	200	Each	Sand Bags
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 126,900.00)
701A227	17	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	9	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	345	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	19	Mile	Broken Temporary Traffic Stripe
701C001	53	Mile	Solid Temporary Traffic Stripe
701G146	1,613	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G148	370	LF	Broken Yellow, Class W, Type A Traffic Stripe
701G154	1,244	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	2,692	LF	Solid Traffic Stripe Removed (Plastic)
703A002	468	SQFT	Traffic Control Markings, Class 2, Type A

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
703B002	46	SQFT	Traffic Control Legends, Class 2, Type A
703D001	952	SQFT	Temporary Traffic Control Markings
705A030	117	Each	Pavement Markers, Class A-H, Type 2-C
705A032	225	Each	Pavement Markers, Class A-H, Type 1-B
705A037	400	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,093	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	500	Each	Cones (36 Inches High)
740M001	500	Each	Ballast For Cone
740O000	1	Each	Pilot Car