

**Alabama Department of Transportation
Proposal Item Summary**

024. RP-STPAA-HSIP-0172(505)

MARION COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 1.00

for constructing the Safety Widening, Micro-Milling, Resurfacing, and Traffic Stripe on SR-172 from the Franklin County Line to the Intersection of SR-17 in Hackleburg. Length 6.013 mi.

The Bracket Estimate on this project is from \$2,518,984 to \$3,078,759.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$15.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	15	SQYD	Removing Concrete Driveway
209A000	1	Each	Mailbox Reset, Single
305B077	1,648	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	21,410	Gal	Tack Coat
408B001	98,079	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A336	5,666	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424A339	147	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424B634	6,953	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B670	500	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B672	5,373	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B677	1,029	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	11	Mile	Scoring Bituminous Pavement Surface
433A000	96,295	SQYD	Scrub Seal
600A000	1	LS	Mobilization
665J002	330	LF	Silt Fence
665O001	330	LF	Silt Fence Removal
665Q002	500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 136,000.00)
701A227	13	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	335	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	12	Mile	Broken Temporary Traffic Stripe
701C001	111	Mile	Solid Temporary Traffic Stripe
701F000	1,465	LF	Dotted Temporary Traffic Stripe
703A002	2,307	SQFT	Traffic Control Markings, Class 2, Type A
703B002	90	SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,173	SQFT	Temporary Traffic Control Markings
705A030	147	Each	Pavement Markers, Class A-H, Type 2-C
705A032	360	Each	Pavement Markers, Class A-H, Type 1-B
705A037	490	Each	Pavement Markers, Class A-H, Type 2-D
705A038	116	Each	Pavement Markers, Class A-H, Type 2-E

Item No.	Quantity	Units	Description
713A000	44	LF	Permanent Barricades
740B000	1,570	SQFT	Construction Signs
740C000	18	SQFT	Special Construction Signs
740D000	75	Each	Channelizing Drums
740O000	1	Each	Pilot Car