

**Alabama Department of Transportation  
Proposal Item Summary**

---

**028. STPAA-0019(507)**

**FRANKLIN COUNTY**

Contract Time: 35 Working Days

DBE Goal Percent: 5.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-19 from the Marion County Line to the junction of SR-172 southeast of Vina. Length 3.600 mi.

The Bracket Estimate on this project is from \$745,810 to \$911,545.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	6,079	Gal	Tack Coat
408B001	60,786	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A340	5,015	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
428A001	8	Mile	Scoring Bituminous Pavement Surface
430B042	563	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type A)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 44,000.00)
701A227	8	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	12	Mile	Solid Temporary Traffic Stripe
703A002	24	SQFT	Traffic Control Markings, Class 2, Type A
703D001	48	SQFT	Temporary Traffic Control Markings
705A032	112	Each	Pavement Markers, Class A-H, Type 1-B
705A037	436	Each	Pavement Markers, Class A-H, Type 2-D
740B000	435	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car