

**Alabama Department of Transportation
Proposal Item Summary**

031. STPAA-0093(503)

PIKE COUNTY

Contract Time: 35 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-93 from the junction of SR-53 (US-231) to the junction of Lakeview Drive in Brundidge. Length 2.429 mi.

The Bracket Estimate on this project is from \$1,083,561 to \$1,324,352.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	6,020	Gal	Tack Coat
408A052	38,575	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
408A053	21,600	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	4,970	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	1,944	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
607D000	17,500	SQYD	Paving Geotextile
607E000	4,400	Gal	Asphalt Sealant
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 58,000.00)
701A227	6	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	999	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	13	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	5,708	SQFT	Traffic Control Markings, Class 2, Type A
703B002	999	SQFT	Traffic Control Legends, Class 2, Type A
703D001	4,208	SQFT	Temporary Traffic Control Markings
703E001	206	SQFT	Temporary Traffic Control Legends
705A030	103	Each	Pavement Markers, Class A-H, Type 2-C
705A032	256	Each	Pavement Markers, Class A-H, Type 1-B
705A037	495	Each	Pavement Markers, Class A-H, Type 2-D
705A038	120	Each	Pavement Markers, Class A-H, Type 2-E
710A160	70	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B021	70	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
740B000	1,339	SQFT	Construction Signs
740C000	9	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car