

**Alabama Department of Transportation  
Proposal Item Summary**

**032. STPAA-0205(511)**

**MARSHALL COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 5.00

for constructing the Micro-Milling, Resurfacing, and Traffic Stripe on SR-205 from the Etowah County Line to the junction of Henderson Avenue in Albertville. Length 2.280 mi.

The Bracket Estimate on this project is from \$1,064,786 to \$1,301,405.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C000	12	SQYD	Removing Concrete Sidewalk
206D003	20	LF	Removing Curb And Gutter
206E039	4	Each	Removing Mailboxes (Including Reset With a New 2 Inch Metal Or 4 Inch Timber Post)
405A000	5,173	Gal	Tack Coat
408B001	64,644	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	5,334	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	198	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	2,500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
618C001	10	SQFT	Detectable Warning Surface
618D000	12	SQYD	Curb Ramp
665G000	50	Each	Sand Bags
665Q002	100	LF	Wattle
666A001	1	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 55,150.00)
701A227	5	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	550	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	8	Mile	Broken Temporary Traffic Stripe
701C001	19	Mile	Solid Temporary Traffic Stripe
703A002	5,166	SQFT	Traffic Control Markings, Class 2, Type A
703B002	206	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,064	SQFT	Temporary Traffic Control Markings
703E001	276	SQFT	Temporary Traffic Control Legends
705A030	50	Each	Pavement Markers, Class A-H, Type 2-C
705A032	254	Each	Pavement Markers, Class A-H, Type 1-B
705A037	304	Each	Pavement Markers, Class A-H, Type 2-D
710A115	36	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type III Or Type IV Background)
710B001	96	LF	Roadway Sign Post (#3 "U" Channel Galvanized Steel)
730H001	3,050	LF	Loop Wire
740B000	1,171	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
740M001	200	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit