

**Alabama Department of Transportation
Proposal Item Summary**

044. STPAA-HSIP-MR22(900)

MOBILE COUNTY

Contract Time: 110 Working Days

DBE Goal Percent: 1.00

for constructing the Safety Widening, Planing, Resurfacing, Steel Blockout Replacement, and Traffic Stripe on I-65 (Service Roads) from the SR-16 (US-90) Interchange in Mobile to the SR-17 (US-45) Interchange in Prichard. Length 12.997 mi.

The Bracket Estimate on this project is from \$2,940,239 to \$3,593,625.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$14.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	17	SQYD	Removing Concrete Sidewalk
206D001	50	LF	Removing Guardrail
206D003	40	LF	Removing Curb And Gutter
206E008	4	Each	Removing Guardrail End Anchor (All Type)
212A000	1,223	STA	Machine Grading Shoulders
405A000	26,526	Gal	Tack Coat
408A052	241,369	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A280	20,954	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424A289	931	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B655	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B659	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	4,181	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	24	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
618A000	2	SQYD	Concrete Sidewalk, 4" Thick
618D000	7	SQYD	Curb Ramp
623C000	40	LF	Combination Curb & Gutter, Type C
630A001	138	LF	Steel Beam Guardrail, Class A, Type 2
630C080	6	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	150	LF	Guardrail Reset
650A000	1,500	CUYD	Topsoil
652A100	5	Acre	Seeding
652C000	30	Acre	Mowing
654A001	500	SQYD	Solid Sodding (Bermuda)
656A010	5	Acre	Mulching
665J002	5,000	LF	Silt Fence
665O001	5,000	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	1	Acre	Pest Control Treatment
674A000	96	LF	Construction Safety Fence
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 166,300.00)
701A227	28	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	15	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	8	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	2,864	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	26	Mile	Broken Temporary Traffic Stripe
701C001	125	Mile	Solid Temporary Traffic Stripe
701G252	2,970	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	8,482	SQFT	Traffic Control Markings, Class 2, Type A
703B002	762	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,358	SQFT	Temporary Traffic Control Markings
705A030	3,609	Each	Pavement Markers, Class A-H, Type 2-C
705A032	609	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,207	Each	Pavement Markers, Class A-H, Type 2-D
705A038	287	Each	Pavement Markers, Class A-H, Type 2-E
730H001	10,280	LF	Loop Wire
740B000	1,319	SQFT	Construction Signs
740D000	150	Each	Channelizing Drums
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit