

**Alabama Department of Transportation
Proposal Item Summary**

055. ATRP2-46-2021-046

MARENGO COUNTY

Contract Time: 90 Working Days

for constructing the Safety Improvements (Roadway Lighting Installation) on SR-8 (US-80) at the Westrock Paper Mill Entrances. Length 1.912 mi.

The Bracket Estimate on this project is from \$612,765 to \$748,935.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
600A000	1	LS	Mobilization
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665Q002	250	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 20,000.00)
740B000	776	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2
750B602	35	Each	Roadway Luminaire Assembly with One, LED, 400 Watt Equivalent Luminaire
750C010	35	Each	Pole Foundation,Roadway
750D200	5	Each	Electrical Junction Box,Type 1
750E127	60	LF	Conduit, 2 Inch, Rigid Metallic
750F026	150	LF	Conductor, #2 AWG
750G010	8,200	LF	Combined Duct And Cable,2 #6 AWG/ 1 #6 AWG GND
750H005	3	Each	Service Pole
750I018	3	Each	Lighting Control Center, Pole Mounted
756A028	725	LF	6" Electrical Conduit, 1 Line, Type 5 Installation