

**Alabama Department of Transportation
Proposal Item Summary**

004. CMAQ-3715(270)

JEFFERSON COUNTY

Contract Time: 125 Working Days

DBE Goal Percent: 3.00

for constructing the Pedestrian Bridge (Grading, Bridge, and Lighting) over SR-150 between Berkley Avenue and Clarendon Avenue in Bessemer. Length 0.039 mi.

The Bracket Estimate on this project is from \$3,063,513 to \$3,744,294.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$15.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 8,000.00 Per Acre) (Approximately 1 Acre)
210A000	5,614	CUYD	Unclassified Excavation
210D011	8,554	CUYD	Borrow Excavation (A4 Or Better)
215B000	1	LS	Cofferdams Or Sheeting And Shoring, Station 1000+10.000
502A000	3,183	LB	Steel Reinforcement
505G003	8	Each	Pile Points (Type A, 12")
505M002	343	LF	Steel Piling Furnished And Driven (HP 12x53)
508A000	840	LB	Structural Steel
510A007	15	CUYD	Bridge Substructure Concrete
516D000	1	LS	Pedestrian Bridge
517D000	1,386	LF	Sidewalk Handrail
529A020	7,667	SQFT	Retaining Wall # 1 (MSE)
529A021	3,800	SQFT	Retaining Wall # 2 (MSE)
529A022	3,335	SQFT	Retaining Wall # 3 (MSE)
529A023	1,497	SQFT	Retaining Wall # 4 (MSE)
539A004	104	LF	12 Inch Trench Drain (With Grate)
600A000	1	LS	Mobilization
614A000	2	CUYD	Slope Paving
618A001	998	SQYD	Concrete Sidewalk, 6" Thick
620A000	46	CUYD	Minor Structure Concrete
637A000	16	LF	Fence Reset
650B000	374	CUYD	Topsoil From Stockpiles
654A000	600	SQYD	Solid Sodding
660D079	20	Each	Trees, Pinus Taeda (Loblolly Pine)
665J002	425	LF	Silt Fence
665O001	425	LF	Silt Fence Removal
674A000	930	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 159,000.00)
740B000	551	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740F001	2	Each	Barricades, Type II
740F002	12	Each	Barricades, Type III
741C010	3	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2
750Z220	1	LS	Roadway Lighting