

**Alabama Department of Transportation
Proposal Item Summary**

014. NH-0001(621)

HENRY COUNTY

Contract Time: 50 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-1 (US-431) from 0.600 mile north of the Houston County Line to the Bay Line Railroad Crossing in Headland. Length 3.112 mi.

The Bracket Estimate on this project is from \$1,772,956 to \$2,166,947.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
210A000	411	CUYD	Unclassified Excavation
405A000	12,341	Gal	Tack Coat
408A052	123,409	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	9,643	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	540	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
432A000	18,233	SQYD	High Density Mineral Bond
600A000	1	LS	Mobilization
652C000	74	Acre	Mowing
654A001	1,496	SQYD	Solid Sodding (Bermuda)
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 93,425.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	7	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	10,994	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	13	Mile	Broken Temporary Traffic Stripe
701C001	47	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G252	3,000	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	4,312	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,864	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,964	SQFT	Temporary Traffic Control Markings
703E001	206	SQFT	Temporary Traffic Control Legends
705A030	1,044	Each	Pavement Markers, Class A-H, Type 2-C
705A037	20	Each	Pavement Markers, Class A-H, Type 2-D
710A160	26	SQFT	Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)
710B021	28	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
730H001	7,250	LF	Loop Wire
740B000	1,872	SQFT	Construction Signs
740C000	14	SQFT	Special Construction Signs
740D000	150	Each	Channelizing Drums

Item No.	Quantity	Units	Description
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2