

**Alabama Department of Transportation
Proposal Item Summary**

017. NH-0006(586)

AUTAUGA COUNTY

Contract Time: 75 Working Days

DBE Goal Percent: 1.00

for constructing the Resurfacing (Micro-Surfacing Seal Coat, Type III), Bridge Guardrail Retrofit, Guardrail Installation, and Traffic Stripe on SR-6 (US-82) from the Chilton County Line to 0.800 mile west of the junction of CR-40. Length 10.172 mi.

The Bracket Estimate on this project is from \$2,844,924 to \$3,477,129.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D000	32	LF	Removing Pipe
206D001	338	LF	Removing Guardrail
206E000	2	Each	Removing Headwalls
206E002	2	Each	Removing Junction Boxes
206E008	28	Each	Removing Guardrail End Anchor (All Type)
210A000	1,200	CUYD	Unclassified Excavation
210D021	800	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	20	CUYD	Structure Excavation
214B001	18	CUYD	Foundation Backfill, Commercial
305B077	660	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
403B001	2,295	Ton	Micro-Surfacing Seal Coat, Type III
405A000	13,430	Gal	Tack Coat
410H000	1	Each	Material Remixing Device
424A360	12,120	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	380	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B693	675	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	20	Mile	Scoring Bituminous Pavement Surface
430B043	1,970	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	75	LB	Steel Reinforcement
505I000	500	SQFT	Temporary Steel Sheet Piling
524B011	2	CUYD	Culvert Concrete Extension (Cast In Place)
530A101	24	LF	18" Roadway Pipe (Class 3 R.C.) (Extension)
600A000	1	LS	Mobilization
610C001	160	Ton	Loose Riprap, Class 2
610D003	550	SQYD	Filter Blanket, Geotextile
619A002	1	Each	18" Roadway Pipe End Treatment, Class 1
620A000	1	CUYD	Minor Structure Concrete
629D002	12	Each	Bridge Guardrail Retrofit, Type BC
630A001	550	LF	Steel Beam Guardrail, Class A, Type 2
630C079	12	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	20	Each	Guardrail End Anchor, Type 20 Series (MASH)

Item No.	Quantity	Units	Description
631C010	600	LF	Guardrail Reset
652A100	1	Acre	Seeding
654A001	140	SQYD	Solid Sodding (Bermuda)
656A010	1	Acre	Mulching
659C001	800	SQYD	Erosion Control Product, Type S3
665A000	2	Acre	Temporary Seeding
665B001	6	Ton	Temporary Mulching
665G000	200	Each	Sand Bags
665J002	1,000	LF	Silt Fence
665N000	50	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	1,000	LF	Silt Fence Removal
665Q002	250	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 170,000.00)
701A227	20	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	13	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	8	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	581	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	18	Mile	Broken Temporary Traffic Stripe
701C001	66	Mile	Solid Temporary Traffic Stripe
701G146	2,213	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,107	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	3,320	LF	Solid Traffic Stripe Removed (Plastic)
703A002	752	SQFT	Traffic Control Markings, Class 2, Type A
703D001	1,504	SQFT	Temporary Traffic Control Markings
705A030	75	Each	Pavement Markers, Class A-H, Type 2-C
705A032	350	Each	Pavement Markers, Class A-H, Type 1-B
705A037	650	Each	Pavement Markers, Class A-H, Type 2-D
726A000	204	LF	Portable Concrete Safety Barriers, Type 6
726A001	10	LF	Portable Concrete Safety Barriers, Type 6-A
726D026	1	Each	Portable Impact Attenuator Assembly (Bi-directional,TL-3)
740B000	1,524	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit