

**Alabama Department of Transportation
Proposal Item Summary**

018. NH-0013(626)

MARENGO COUNTY

Contract Time: December 31, 2022 Completion Date

DBE Goal Percent: 2.00

for constructing the Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-13 (US-43) from the junction of 12 Link Road to the junction SR-8 (US-80) in Demopolis. Length 6.669 mi.

The Bracket Estimate on this project is from \$1,969,750 to \$2,407,472.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	7,415	Gal	Tack Coat
408B001	129,900	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A361	10,990	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	650	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	14	Mile	Scoring Bituminous Pavement Surface
430B043	450	Ton	Aggregate Surfacing (1" Down, Crusher Run)
433A000	87,250	SQYD	Scrub Seal
600A000	1	LS	Mobilization
650A000	500	CUYD	Topsoil
652A100	6	Acre	Seeding
652C000	32	Acre	Mowing
656A010	6	Acre	Mulching
665Q002	200	LF	Wattle
666A001	6	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 105,000.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B205	395	LF	Dotted, Class 2, Type A, Traffic Stripe
701C000	15	Mile	Broken Temporary Traffic Stripe
701C001	67	Mile	Solid Temporary Traffic Stripe
703A002	417	SQFT	Traffic Control Markings, Class 2, Type A
703B002	90	SQFT	Traffic Control Legends, Class 2, Type A
703D001	600	SQFT	Temporary Traffic Control Markings
705A030	312	Each	Pavement Markers, Class A-H, Type 2-C
705A032	227	Each	Pavement Markers, Class A-H, Type 1-B
705A037	658	Each	Pavement Markers, Class A-H, Type 2-D
740B000	992	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone

Item No.	Quantity	Units	Description
7400000	1 Each	Pilot Car	