

**Alabama Department of Transportation  
Proposal Item Summary**

**030. STPAA-0027(518)**

**GENEVA COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Micro-Milling, Resurfacing, Guardrail Installation, and Traffic Stripe on SR-27 from the Florida State Line to the junction of SR-52 in Geneva. Length 5.950 mi.

The Bracket Estimate on this project is from \$1,626,794 to \$1,988,304.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	1,513	LF	Removing Guardrail
206E008	8	Each	Removing Guardrail End Anchor (All Type)
206E014	4	Each	Removing Guardrail End Anchor (Type 2A)
405A000	11,694	Gal	Tack Coat
408B001	111,374	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A361	8,890	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	300	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	10	Mile	Scoring Bituminous Pavement Surface
430B043	221	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
629D003	4	Each	Bridge Guardrail Retrofit, Type SC
630A001	1,400	LF	Steel Beam Guardrail, Class A, Type 2
630A034	38	LF	Steel Beam Guardrail, Class A, Type 2 (8'-0" Post)
630C079	4	Each	Guardrail End Anchor, Type 13 (MASH)
630C080	8	Each	Guardrail End Anchor, Type 20 Series (MASH)
652C000	30	Acre	Mowing
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 87,000.00)
701A227	11	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	602	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	18	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	2,778	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	2,778	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	5,444	SQFT	Traffic Control Markings, Class 2, Type A
703B002	180	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,109	SQFT	Temporary Traffic Control Markings
703H000	24	SQFT	Specialty Traffic Control Markings

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
705A030	50	Each	Pavement Markers, Class A-H, Type 2-C
705A032	328	Each	Pavement Markers, Class A-H, Type 1-B
705A037	553	Each	Pavement Markers, Class A-H, Type 2-D
705A038	346	Each	Pavement Markers, Class A-H, Type 2-E
730H001	2,250	LF	Loop Wire
740B000	1,614	SQFT	Construction Signs
740C000	14	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car