

**Alabama Department of Transportation  
Proposal Item Summary**

**035. STPAA-0088(501) & NH-0134(512)**

**COFFEE COUNTY**

Contract Time: 45 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-88 from the junction of SR-12 (US-84) to the junction SR-167 in Enterprise (Site 1) and on SR-134 from the junction of SR-88 to the junction of SR-12 (US-84) in Enterprise (Site 2). Length 4.089 mi.

The Bracket Estimate on this project is from \$1,630,951 to \$1,993,385.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$14.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
405A000	12,524	Gal	Tack Coat
408A052	115,244	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	9,517	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	229	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 87,500.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	5	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B063	950	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	3,463	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	16	Mile	Broken Temporary Traffic Stripe
701C001	39	Mile	Solid Temporary Traffic Stripe
701D007	2	Mile	Solid Traffic Stripe Removed (Paint)
701D008	2	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	2	Mile	Broken Traffic Stripe Removed (Paint)
701D015	2	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	15,860	SQFT	Traffic Control Markings, Class 2, Type A
703B002	1,306	SQFT	Traffic Control Legends, Class 2, Type A
703D001	7,443	SQFT	Temporary Traffic Control Markings
703E001	1,366	SQFT	Temporary Traffic Control Legends
703H000	621	SQFT	Specialty Traffic Control Markings
705A030	993	Each	Pavement Markers, Class A-H, Type 2-C
705A031	192	Each	Pavement Markers, Class A-H, Type 1-A
705A032	520	Each	Pavement Markers, Class A-H, Type 1-B
705A037	187	Each	Pavement Markers, Class A-H, Type 2-D
705A038	410	Each	Pavement Markers, Class A-H, Type 2-E
730H001	14,175	LF	Loop Wire
740B000	1,964	SQFT	Construction Signs
740C000	68	SQFT	Special Construction Signs
740E000	200	Each	Cones (36 Inches High)

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit