

**Alabama Department of Transportation
Proposal Item Summary**

043. STPAA-HSIP-FMGR-0053(595)

ST. AND CLAIR COUNTIES

Contract Time: 30 Working Days

for constructing the Resurfacing (Surface Treatment), Guardrail Safety Improvements, and Traffic Stripe on SR-53 (US-231) from the Shelby County Line to the junction of SR-34 in Pell City. Length 9.789 mi.

The Bracket Estimate on this project is from \$1,044,035 to \$1,276,043.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E008	2	Each	Removing Guardrail End Anchor (All Type)
210D001	40	CUYD	Borrow Excavation (Loose Truckbed Measurement)
403B000	1,109	Ton	Micro-Surfacing Seal Coat, Type II
403B001	1,700	Ton	Micro-Surfacing Seal Coat, Type III
428A001	19	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
630C080	2	Each	Guardrail End Anchor, Type 20 Series (MASH)
631C010	500	LF	Guardrail Reset
650A000	16	CUYD	Topsoil
654A001	60	SQYD	Solid Sodding (Bermuda)
665J002	100	LF	Silt Fence
665O001	100	LF	Silt Fence Removal
665Q002	100	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 56,000.00)
701A227	20	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	9	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,087	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	17	Mile	Broken Temporary Traffic Stripe
701C001	53	Mile	Solid Temporary Traffic Stripe
703A002	1,749	SQFT	Traffic Control Markings, Class 2, Type A
703B002	202	SQFT	Traffic Control Legends, Class 2, Type A
703D001	164	SQFT	Temporary Traffic Control Markings
705A030	59	Each	Pavement Markers, Class A-H, Type 2-C
705A031	84	Each	Pavement Markers, Class A-H, Type 1-A
705A032	629	Each	Pavement Markers, Class A-H, Type 1-B
705A037	695	Each	Pavement Markers, Class A-H, Type 2-D
705A038	234	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,064	SQFT	Construction Signs
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
740O000	1	Each	Pilot Car