

**Alabama Department of Transportation  
Proposal Item Summary**

**009. IM-1065(520)**

**BUTLER COUNTY**

Contract Time: 60 Working Days

for constructing the Widening, Micro-Milling, Resurfacing, and Traffic Stripe on I-65 from 0.870 mile north of the junction of Pettibone Road to the junction of CR-41 northeast of Greenville. Length 7.259 mi.

The Bracket Estimate on this project is from \$3,203,372 to \$3,915,232.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity Units	Description
405A000	1,000 Gal	Tack Coat
408B000	227,520 SQYD	Micro-Milling Existing Pavement (Approximately 0.00" Thru 1.00" Thick)
410H000	1 Each	Material Remixing Device
420A015	10,750 Ton	Polymer Modified Open Graded Friction Course
420B000	35,840 Gal	Open Graded Friction Course Tack Coat
424A278	500 Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 3/8" Maximum Aggregate Size Mix, ESAL Range E
424B283	500 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range E
432A000	117,130 SQYD	High Density Mineral Bond
600A000	1 LS	Mobilization
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 170,000.00)
701A227	15 Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	15 Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	15 Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	4,710 LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	45 Mile	Broken Temporary Traffic Stripe
701C001	90 Mile	Solid Temporary Traffic Stripe
701G142	1,373 LF	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701G146	1,373 LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,373 LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	2,746 LF	Solid Traffic Stripe Removed (Plastic)
701H006	1,373 LF	Broken Traffic Stripe Removed (Plastic)
703A002	10,216 SQFT	Traffic Control Markings, Class 2, Type A
703D001	30,646 SQFT	Temporary Traffic Control Markings
705A030	1,632 Each	Pavement Markers, Class A-H, Type 2-C
705A031	1,239 Each	Pavement Markers, Class A-H, Type 1-A
705A032	2,268 Each	Pavement Markers, Class A-H, Type 1-B
740B000	3,679 SQFT	Construction Signs
740C000	72 SQFT	Special Construction Signs
740D000	700 Each	Channelizing Drums
740E000	500 Each	Cones (36 Inches High)
740M001	500 Each	Ballast For Cone
741C010	2 Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	8 Each	Portable Changeable Message Sign, Type 2