

**Alabama Department of Transportation  
Proposal Item Summary**

**021. RP-STPAA-HSIP-0017(587)**

**LAMAR COUNTY**

Contract Time: 40 Working Days

DBE Goal Percent: 1.00

for constructing the Safety Widening, Micro-Milling, Resurfacing (Scrub Seal), and Traffic Stripe on SR-17 from 0.340 mile east of the junction of Payne Chapel Road to a point south of the Luxapalila Valley Railroad (MP 229.156) in Millport. Length 2.143 mi.

The Bracket Estimate on this project is from \$1,991,665 to \$2,434,258.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C010	214	SQYD	Removing Concrete Driveway
209A000	3	Each	Mailbox Reset, Single
305B077	910	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
401B108	7,834	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	14,124	Gal	Tack Coat
408A056	7,870	SQYD	Planing Existing Pavement (Approximately 5.10" Thru 6.0" Thick)
408B001	60,026	SQYD	Micro-Milling Existing Pavement (Approximately 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
410I000	1	Each	Smoothness Testing, Certified Inertial Profiler
424A356	2,807	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	60	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B002	3,594	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1/2" Maximum Aggregate Size mix, ESAL Range C/D
424B657	25	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	3	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B685	4,802	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B687	63	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	235	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	2	Mile	Scoring Bituminous Pavement Surface
433A000	34,830	SQYD	Scrub Seal
600A000	1	LS	Mobilization
665Q002	100	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 107,200.00)
701A227	5	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	2	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,242	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	7	Mile	Broken Temporary Traffic Stripe
701C001	42	Mile	Solid Temporary Traffic Stripe
701H002	120	LF	Solid Traffic Stripe Removed (Tape)
703A002	9,801	SQFT	Traffic Control Markings, Class 2, Type A
703B002	338	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,861	SQFT	Temporary Traffic Control Markings

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
703E001	274	SQFT	Temporary Traffic Control Legends
705A030	115	Each	Pavement Markers, Class A-H, Type 2-C
705A032	1,060	Each	Pavement Markers, Class A-H, Type 1-B
705A037	250	Each	Pavement Markers, Class A-H, Type 2-D
705A038	520	Each	Pavement Markers, Class A-H, Type 2-E
730H001	284	LF	Loop Wire
740B000	1,240	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car
742A001	2	Each	Portable Changeable Message Sign, Type 2